

Veridian Petrochemicals
Dahej Tank Farm

Document no: MLS-TL-OM Revision: A
Title: Operation manual, MLS-TL top-loading arms
Owner: Dr. Sunita Rao
Issued: 26 February 2024

Primary equipment: LA-6101, Truck loading arm 1

Applies to LA-6101 to LA-6103 (tank farm) and LA-5101 to LA-5104 (blending and dispatch).
Earthing check required before connection. Swing joint inspection every 12 months; grounding
continuity test every 6 months. Vapour return interlock must be proven before loading starts.